BERGMARK GUIMOND HAMMARLUND JONES ARCHITECTS

P.O. Box 1719, 63 Fitzroy Street
Charlottetown, PE
C1A 7N4
Tel: 566-4449 Fax: 566-1235
e-mail: info@bghj.com

ADDENDUM #2

Date:	February 22, 2017	
Project:	Riverview Long Term Care Facility	
Project #:	15010	
Re:	Addendum #2	**2 Page Addenda – 0 Attachments**

This addendum forms part of the Contract Documents and is to be read, interpreted and coordinated with all other parts. The following items and prices shall be added to the tendered price for this project.

General

A-2.1 ***All trades are to review addendum in its entirety.***

Specifications

A-2.3 Ref.: Section 00 21 13 – Instruction to Bidders

.1 Add Para. 1.2.1.13
All storm water or pumped water is to be placed within the sediment pond located within site boundaries. TP 1 is responsible for the development and construction of this pond.

.2 Add Para. 1.2.2.11
All storm water or pumped water is to be placed within the sediment pond located within site boundaries. TP2 is responsible to pump water (as required for own work) to this pond.

.3 Add Para. 1.2.2.12
This package <u>does not</u> include exterior slab on grade, interior slab on grade, interior lift pit base, interior freezer base, or interior biomass pit. These will be included in future trade packages.

A-2.4 Ref.: Section 00 41 00 – Trade Contract Tender Form
Para. Schedule of Work:

.1 TP 1 (site fill) – building pad structural fill to be completed enough to allow foundation start by May 15th.

.2 TP 2 (foundation) – foundation start May 15th. Completion is expected within 9 weeks

A-2.5 Ref.: Section 03 30 00 – Cast-in-Place Concrete
Add Para. 2.1.17.1
Approved Equal: Pecora Dynatrol II by Pecora Corporation

A-2.6 Ref.: Section 03 35 00 – Concrete Finishing

.1 Add Para. 2.1.4.1.1
Approved Equal: MasterSeal CR100 by BASF

.2 Add Para. 2.1.4.2.1
Approved Equal: Pecora DynaFlex by Pecora Corporation

.3 Add Para. 2.1.5.1
Approved Equal: Denepox I-40 by Grace Construction Products

.4 Add Para. 2.1.6.1
Approved Equal: MasterEmaco ADH 326 by BASF

Drawings

A-2.7 Ref.: Drawing S1 Gridline E/12 and Gridline 10
Section 28/S1/S3 is called out regarding Grid E/12 and Grid D/9-12 (10) to indicate where Biomass Pipe passes through footings at these locations. Note footing at J/12-13 is dropped where Biomass Pipe passes through foundation wall.

END