

ADDENDUM #3

PROJECT: Royalty Centre Accessibility Improvements
TIE # 2860-19047

DATE: July 29, 2019

This addendum forms part of the Contract Documents and is to be read, interpreted and coordinated with all other parts. The following items and prices shall be added to the tendered price for this project.

Page 1 of 1

1. Refer to Drawing A3, Details

.1 Refer to New Entrance 107 & 108

The finish ceiling height of the new Vestibule shall be to match existing ceilings at 10' AFF. Ceiling in Vestibule and in Waiting Area adjacent to the Vestibule is painted gypsum board. Provide new painted gypsum board ceiling in Vestibule at 10' AFF and repair ceiling outside Vestibule as required by construction of new, larger vestibule. Reinstate ceiling recessed heat unit and recessed light. Supply and install new ceiling-mounted EXIT light.