

PROJECT Parkside Elementary School Air Exchange Upgrade 195 Summer St., Summerside, PE TI Project No. 440-20080	PROJECT NO. 20-193
DESCRIPTION Addendum No. 2	DATE April 1, 2021

Item No. 1 Reference Section 1A – General Instructions

- .1 Clarification – Par. 14 b:
Asbestos abatement is a requirement in the project scope and shall be included in Tender as stated in specifications.

Item No. 2 Reference Drawing M-1

- .1 Change – Office Area ductwork:
Delete 150 mm exhaust duct branch serving washroom. The existing standalone washroom exhaust fan serving space shall remain.

Item No. 3 Reference Drawing M-3

- .1 Change – Par. 3.9:
ERV-1, 2, and 4 shall be provided with 2” MERV 13 filters (2 complete sets). ERV-3 filter requirements unchanged.

Item No. 4 Reference Drawing E-1

- .1 Clarification – Panel H location:
Panel H location in Bookroom 216 shall be shifted to the right along same wall, towards Library, to minimize disturbance with existing space furnishings and shelving.
- .2 Clarification – ERV-3:
Replace the manual motor switch with a duplex 5-15R receptacle located adjacent to the unit.
- .3 Clarification – Electrical Notes:
New electrical conduit installed in Basement will not be required to be painted.

Item No. 5 Acceptable Products

The following manufacturers are accepted as suppliers of the items listed. In each case it is the responsibility of the manufacturer to select specific products that meet the specifications in all significant respects. Products offered will be subject for review and acceptance at the shop drawing stage. Contractors are to satisfy themselves that products offered meet the specifications and fit in the available space as no extra charge will be considered if they are later found to be unsuitable.

M-3 Par. 3.6 Grilles & Diffusers Airvector